# BURKE CREEK RABE MEADOW RIPARIAN RESTORATION PROJECT STATELINE, NEVADA

Nevada Tahoe Conservation District 400 Dorla Ct., PO Box 915 Zephyr Cove, Nevada 89448 (775) 586-1610

The following modifications are hereby made to the Bidding and Contract documents for the above referenced project:

### **CHANGES TO THE BID DOCUMENTS**

**ITEM 1:** Kahle Ditch backfill compaction should be per detail 3 on page D1.4 of the Project Plans. Detail 1 on page D1.2 should reference this detail. Backfill compaction levels will be assessed through visual inspection of methods and spot compaction tests performed by Engineer.

**ITEM 2:** Detail 4 on page D1.4 of the Project Plans for Pond Backfill shall include a call out for the native fill compaction that says "Pond backfill composed of native borrow at 90% compaction."

**ITEM 3:** Section 200.06 Channel and Bed Material in the Special Technical Provisions shall be revised to state: "Channel Bed *and Pond Bed* Material shall be a mix of 50 percent of the Well Graded Gravel Mixture in Section 200.05 and 50 percent of the Sand in Section 200.04."

**ITEM 4:** Section 260.06 Revegetation Treatment Types in the Special Technical Provisions shall be revised to state the following to correct the discrepancy with the bid list:

## **Upland Treatment**

Have Engineer check for any areas of excessive compaction. De-compact as necessary to 6" depth and rake smooth. See with Upland Seed Mix. Install single layer of straw coconut erosion control blanket on slopes 3:1 or greater, **15,000** square feet of erosion control blanket maximum to be installed. Mulch remaining areas with 1 to 2 inch layer of mulch.

### **CLARIFICATION ITEMS**

**CLARIFICATION ITEM 1:** A signed copy of Addendum 1 shall be attached to and submitted with the bid proposal.

**CLARIFICATION ITEM 2:** Irrigation water will be provided free of charge by the Tahoe Beach Club. An existing irrigation box is located on the same side of the existing beach club access road as the project across from Tahoe Beach Club Building 1, approximately 500' upstream from the downstream end of the project.

**CLARIFICTION ITEM 3:** The Nevada Tahoe Conservation District will cooridinate with the contractor for the Tahoe Beach Club to remove or relocate the existing erosion control filter fence that conflicts with the Project access and construction prior to the Burke Creek Rabe Meadow Riparian Restoration Project starting.

**CLARIFICATION ITEM 4:** Lam Watah compaction shall be per note 3 on detail 1 on page D1.4 of the project plans. This compaction level is expected to be approximately 90 percent MDD.

# ADDENDUM NO. 1, Page 2 of 2

END OF ADDENDUM	
Name of Firm:	Date:
By:	