

**KAHLE WATER QUALITY BASIN IMPLEMENTATION PROJECT  
STATELINE, NEVADA**

Nevada Tahoe Conservation District  
400 Dorla Ct., PO Box 915  
Zephyr Cove, Nevada 89448  
(775) 586-1610

---

The following modifications are hereby made to the Bidding and Contract documents for the above referenced project:

**CHANGES TO THE BID DOCUMENTS**

**ITEM 1:** In the Plan Set on Sheet D-1, detail 2/D-1 for the Fiber Roll Silt Barrier, Note 1 should be replaced with the following language: "Fiber rolls shall not be made from straw, with the exception of weed-free rice straw. Fiber rolls shall have a minimum weight of 2.5 lbs per linear foot. Fiber rolls shall be removed at the end of construction as directed by the Engineer."

**CLARIFICATION ITEMS**

**CLARIFICATION ITEM 1:** A signed copy of Addendum 3 shall be attached to and submitted with the bid proposal.

**CLARIFICATION ITEM 2:** In the Plan Set on Sheet D-3, detail 3/D-3 for the Willow Wattling Detail, the detail calls out using "Fresh Dormant Branches," which may not be available at the time of construction. The Contractor shall install the willow wattles no sooner than September 1. The Engineer and Revegetation Specialist will mark an area for willow branch harvest no more than 100 feet from the location of the proposed wattles.

**END OF ADDENDUM**

Name of Firm: \_\_\_\_\_ Date: \_\_\_\_\_

By: \_\_\_\_\_